

Bill No. AU HEADQUARTER: testing of New 8" Unisectional One Borehole
Envisaged depth: 150m

Item No.	Description	Unit	Qty	Rate	Amount
				ETB	ETB
3	Test pumping				
3.1	Carry out step drawdown tests as specified in TSP and as directed by the engineer	hr	6		
3.2	Carry out step recovery tests as specified in TSP and directed by the engineer	hr	2		
3.3	Carry out constant discharge test as specified in TSP and as directed by the engineer	hr	48		
3.4	Carry out recovery tests after constant discharge test as specified in TSP and directed by the engineer	hr	12		
	Subtotal carried to summary				
4	Water quality test				
4.1	Taking water samples and Carry out water quality analyses from borehole at any depth, including provision of sampling bottles and other containers all as specified in the TSP and directed by the Engineer	Nr	2		
	Subtotal carried to summary				
5	Miscellaneous items				
5.1	Standing time spent by the Contractor's equipment and crew while waiting for instructions from the Engineer (excluding idle time due to negligence by the Contractor)	Hr	Rate only		
5.2	Preparation and submission of borehole completion report as specified in TSP	LS			
5.3	Site clearing and levelling, including site clean up after completion of works	Nr	1		
	Subtotal carried to summary				
Total Bill Summary					